


NOTES

1. VALVE BOX SHALL BE ADJUSTED TO THE FINISHED GRADE PRIOR TO PLACING OF THE ASPHALTIC CONCRETE SURFACE.
2. USE PARKSON TYLER, APCO, OR EQUAL DEEP SKIRTED LID (4" OR MORE) TYPE, SLIDING ADJUSTABLE CAST IRON VALVE BOX. C.I. MIN. T.S. 30,000 P.S.I.
3. GROUND BELOW CONCRETE PAD OR 3 BRICKS TO BE COMPACTED 95% OF MAX. DENSITY.



DETAIL NO.
G-3320-1

CITY OF GOODYEAR
STANDARD DETAIL

APPROVED BY:
Goodyear Standards and
Policies Committee 7/97

VALVE BOX INSTALLATION AND
GRADE ADJUSTMENT

DETAIL NO.
G-3320-1

